



### ICEC27-ICCC 2018 27th International Cryogenic Engineering Conference International Cryogenic Materials Conference 2018 September 3-7 2018 Oxford England

# Commissioning and performance of the cryogenic system of the new test facility for large superconducting devices at CERN

<u>J.H. Derking</u>, A. Perin, T. Dupont, B. D'Hulster, K. lakovidis, L. Stewart, T. Barbe and M. Pezzetti

CERN, Technology Department, Cryogenics Group, 1211 Geneva 23, Switzerland

On behalf of all people of the project team at CERN and GSI Research Center

ICEC 2018 Conference September 4<sup>th</sup>, 2018 E-01: 072

### Outline

Introduction

Description of the cryogenic system

Commissioning and performance

Compression building refurbishment

Conclusions with project status



### **GSI-FAIR Super-FRS magnet tests at CERN**

In the framework of a collaboration agreement between CERN and GSI, **57 Super-FRS** magnets will be tested at CERN at 4.5 K: 48 multiplets and 9 dipoles.

Mass up to **70 tons** and dimensions up to **5 m** high

The test sequence is planned to last about 42 days for each magnet.

The required test rate is 21 magnets / year

The super-FRS magnet tests are the main driver for the architecture of the new test facility

Туре	#	Total mass [kg]	Cold mass [kg]
dipole	24	50'000	2'000
multiplet 1	24	70'000	45'000
multiplet 2	9	25'000	20'000

#### See also:

A. Perin et al. CEC 2015, Mat. Sci. Eng. **101** p. 012185 J.H. Derking et al. CEC 2015, Mat. Sci. Eng. **101** p. 012104



CERN

Slide of 3 / 18

### The new test facility for large devices

#### Located in 2 buildings:

B279: compression stations B180: 1400 m<sup>2</sup> for cryogenics and tests

#### The facility can accommodate devices:

- Up to **55 tons, 7 m** high max
- Up to **89 tons, 5 m** high max



#### Dimensioning parameters for performing the test sequence for a multiplet 1 (heaviest magnet)

Test Phase	Requirement
Cool-down 293 K – 90 K	5.6 kW cooling power, 21.4 g/s at 10 bar
Cool-down 90 K – 4.5 K	6.2 m <sup>3</sup> of saturated LHe at 4.5 K
Filling of magnet with LHe	1.7 m <sup>3</sup> of saturated LHe at 4.5 K
Cold tests heat loads	30 W static at 4.5 K + 35 W dynamic during10 minutes 160 W at 60 K – 70 K (screen) 1.6 g/s at 4.5 K = 300 K (liquefaction load)
	1.6 g/s at 4.5 K – 300 K (liquefaction load)
Warm-up 90 K – 293 K	5.4 kW heating, 20 g/s at 10 bar



### 3D overview of test facility






ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 5 / 18

# Configuration of cryogenic system



DVB: Distribution Valve Box

SVB: Satellite Valve Box


CVB: Connection Valve Box


CWU: Cool down / Warm up Unit



ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 6 / 18





ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 8 / 18

### B180 test facility: overview







ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 9 / 18

### Helium refrigerator

An existing **Sulzer TCF200** helium refrigerator of 1979 was fully refurbished by *Linde Kryotechnik* in 2016.

Brayton cycle with **two** turbines in series. **Third** turbine for boosting performance.

<u>Original performance:</u> 1.2 kW refrigeration or 5.6 g/s liquefaction with 1.0 kW shield between 60 – 90 K.

#### Main refurbishment work included:

- Adding a GHe return to 300 K;
- New purge and instrumentation rack;
- New cooling water distribution panel and turbine bearing gas supply panel;
- New turbine coolers;
- Maintaining all cryogenic valves;
- Repairing thermometers;
- Repainting the box.







### Helium refrigerator compression station

A new compression station from *Mayekawa Italy* S.R.L. is used for driving the helium refrigerator.

#### Main components:

- Two stage compound screw compressor;
- One 3.3 kV AC electrical motor;
- Oil separation system with oil separator, 3 coalescing filters and a charcoal adsorber.

#### Design performance:

Supply pressure: 18.7 bar

Suction pressure: 0.9 bar

GHe flow rate: 160 g/s

Electrical power: 706 kW



Helium refrigerator compression station







Slide of 11 / 18

# Helium refrigerator: commissioning results

#### Helium refrigerator compression station

**Helium refrigerator** 





Supply pressure: 17.2 bar Suction pressure: 1.0 bar Max flow rate: 185 g/s Consumed electrical power: 637 kW Supply pressure: 17.2 bar Suction pressure: 1.0 bar Refrigeration power: 1300 W @ 160 g/s Liquefaction power: 6.9 g/s @ 125 g/s No shield cooling



Slide of 12 / 18

# B180: cryogenic distribution system

5 m<sup>3</sup> LHe dewar delivered by *Cryoworld BV* Preliminary measured evaporation rate:

~1.4% / day of total capacity or 2.0 W







Cryodistribution delivered by *Kriosystem* First cool down in autumn 2017 to test:

- Mechanical integrity
- Leaks
- Vacuum jacket temperature

No major non-conformities found.



ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 13 / 18

## Precooling & warming up system


Purpose cool-down / warm up units:

- precool devices to 80 K;
- warm up devices from 4.5 K to room temperature.

50 g/s GHe circulation at 10 bar 15 kW cooling capacity with  $\Delta$ T of 50 K (LN<sub>2</sub>) 15 kW heating capacity

Includes 80 K adsorber to remove gas impurities

<image>








ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 14 / 18

### Compression station building 279: overview



Compression building B279 was built in 1971.

The building is fully renovated to fulfil current standards with respect to safety and environmental aspects.





May 2016

ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 15 / 18

# B279: oil spillage measures

Oil spillage measures taken to:

- collect the total amount of oil (2000 L)
- prevent leakage outside the building (through cracks, drainages etc.)




Resign on floor



Profiles at corners

Mapping floor level



Steps at doors and openings



Collector pipe at lowest point of floor



#### Gutters





Retention tank 2: 1900 L



ICEC-ICMC 2018 / E-01: 072 September 4<sup>th</sup>, 2018

Slide of 16 / 18

# B279: noise measures

Noise **outside** the building needs to stay **below 60 dB(A)** due to proximity of offices.

A study determining the noise damping coefficients showed that we need **below 90 dB(A) inside** the building.

#### Noise sources:

Helium refrigerator compression station: 98 dB(A) CWU compression station: 88 dB(A)

#### Two options:

- 1) Isolating the building -> complex and costly
- 2) Noise hood around compressor stages helium refrigerator compression station

**Option 2 selected**. Noise hood reduces noise to 90 dB(A) at 1 m of compression station.







#### Noise hood



Slide of 17 / 18

### Conclusions

CERN has built a cryogenic test facility for large and heavy superconducting devices. It will be firstly used to test the FAIR Super-FRS magnets.

The LHe production and distribution system were installed and successfully commissioned. The performance corresponds well to the design parameters.

The cool down / warm-up units are installed and commissioning is ongoing.

Test facility is currently in final assembly and commissioning. First magnet prototype arrives in autumn 2018. Series testing in planned to start in autumn 2019.



# Thank you for your attention Questions?



www.cern.ch