




Installation, alignment, and commissioning of primary and secondary beamline components for LBNF

Žarko Pavlović

09/20/2022


Past experience

- Installation and commissioning plans building on past experience (particularly NuMI)
- NuMI beam extracted from Main Injector into 350m long transport line
- NuMI commissioning
 - Transport line in the MI tunnel completed during 12 week shutdown in 2004
 - 3 short commissioning runs
 - Dec 2004 - Extracted beam, hit absorber on 10th pulse (target not inserted)
 - Jan 2005 - Beam with target and horns on
 - Feb 2005 - Higher intensity beam delivered



LBNF

- Primary protons 60-120 GeV
- Initially 1.2MW, upgradeable to 2.4MW
- ~370m proton transport line+~220m target hall/decay pipe
- Near detector @570m, and Far detector @1300km (~1500m deep)




Requirements

- Require well controlled neutrino beam with minimal systematic errors
- No significant contribution to neutrino flux systematic error or impact on physics measurements
- Tolerances
 - Proton beam angle: $70 \mu\text{rad}$
 - Proton beam position: 0.5mm, profile: 10%
 - Baffle beam scraping: 1%
 - Target and Horn A/B/C displacement (transverse/tilt): 0.5mm

Instrumentation

- Beam Position Monitors, Profile Monitors, Toroids, Beam Loss Monitors
- Target Position Thermometer (Hyllen device)
- BLMs in target hall (for Beam Based Alignment)
- Hydrostatic/Horn Leveling System (HLS)
 - Monitor vertical shifts of beamline components (BPMs, Baffle, Horns; both in primary and secondary beamline)
- Hadron monitor (HADeS) and Muon monitors (MuMS)


Alignment



- Use MI extraction point and the Homestake Mine as reference points in Fermi coordinate system to establish the beamline trajectory
- In 2016 comprehensive surveying campaign took place to refine the global positions of FNAL and the 4850 Level of the Sanford Lab
 - Surface GPS network accuracy is within ± 10 mm
 - Transfer to 4850ft level using 1 mile long plumb line
- Build network in the enclosures
- Components alignment requirements very similar to NuMI:
 - Primary beam magnets and instrumentation aligned to ± 0.25 mm
 - Target station components aligned to ± 0.5 mm
- Survey and rough alignment as components are installed

Primary Beam Installation

- Install:
 - LCW pipes and bus
 - Magnet stands and align
 - six degrees of freedom for precise adjustment
 - Magnets and rough align
 - Beam tube and instrumentation
 - Beam Position Monitors, Beam Loss Monitors, Toroids, Profile Monitors, HLS
- Magnet installation and support based on NuMI and MI experience (with some modifications)
- In parallel outfit the support building (power supplies, pumps, etc), cable everything
- Reconfigure MI for extraction (kickers, lambertsons, extraction dipoles and quads)
- Ramp magnets, pull vacuum, and final alignment




Beam permit system

- Commission the beam permit system
- Prevents beam delivery under any fault condition
- Taking input from beamline instrumentation
- Predict initial limits for signals based on:
 - Specifications of power supplies
 - MARS studies
 - Accelerator studies
 - Desired operational values

Beam extraction

- Setup alarms & limits
- Ensure devices are reading back, data logging, BPS active,
- Extract the beam from MI and down the beam-line, get the beam to hadron absorber
- Low intensity, multiwires in
- Time in the kicker
- Adjust trims to “walk” the beam down the beamline
- Optimize major bend currents; hopefully do not need to realign
- Adjust autotune

NuMI on 10th pulse





Beam Based Alignment (BBA)

- Final alignment of the neutrino beam components is done with scans of the proton beam across the components
 - Heavy shielding may cause components to shift and direct survey no longer possible
 - Thermal expansion
 - Beam position monitors calibration drift
- Study done with special beam conditions
 - Use 1 mm sigma beam spot size for scanning
 - Low intensity and low rate
 - Scan beam parallel to nominal beam axis, up/down and left/right, +/- 25 mm
- Done in several steps (Beam direction, Baffle, Horn B&C, Target, Final alignment)
- Using HADeS and Beam Loss Monitors




BBA

Beam direction

- Horn/target not in the beam
- Baffle in “clear shot” position
- Aim the beam at the hadron absorber, establish the beam center
- HADeS precision at 1.5cm
- With lever arm $\sim 220\text{m}$ lever arm, get $<70 \mu\text{rad}$ precision




Baffle positions



<i>“Baffle BBA” Position</i>	<i>“Clear Shot” Position</i>	<i>“On-Axis” Position</i>
		
<p>NB no Target / Horn-A in Chase</p> <p>Baffle driven to “Baffle BBA” position</p> <p>Beam-scan baffle BBA features, perform angular alignment</p>	<p>Baffle raised to “clear-shot” position</p> <p>Enables BBA of downstream components</p>	<p>Baffle lowered to “on-axis” position</p> <p>Beam-scan baffle bore to verify correct position prior to running high intensity beam</p>

BBA

Baffle scan






- Baffle moved to angle alignment position
- Scan beam across fins and determine position using HADeS
- Infer position after subsequent moves using module motor drives and LVDT position readback
- Require alignment within 2mm with respect to the target (follows from $<1\%$ baffle beam scraping requirement and adequate protection of downstream elements)



BBA

Horns B&C



- Scan across the cross hairs
- Using primarily BLMs
- BLMs installed in 4 planes with each one following horn US/DS cross hair



BBA

Target




- Scan beam over target/bafflet
- Bafflet (0.18m) is on upstream end of target (1.5m) - clear difference in HADeS signal
- X, Y position of bafflette edges, and of target mass centroid
- Determines target position and angle



BBA


Final scan

- Baffle moved to in beam position
- Final scan, confirm baffle position
- Confirm beam centered on target using TPT as ramping intensity



Horns on

- Beam on target, horns powered
- HADeS out of the beam for normal running
- Observe the muon flux in muon monitors
 - Flux increase as ramping up horn current
- Keep raising intensity



Summary

- LBNF will provide an intense and well controlled neutrino beam for DUNE experiment
- Installation, alignment and commissioning builds on extensive experience with neutrino beams at Fermilab (NuMI in particular)
- Alignment requirements are similar to NuMI
- Beam based alignment procedure provides precise placement of beamline components and beam direction
- Instrumentation designed to allow Beam Based Alignment and meet the monitoring needs to satisfy the requirements