

J-PARC Neutrino Extraction Beamline Instrumentation

Megan Friend

High Energy Accelerator Research Organization (KEK)


NBI2022, September 20, 2022

Outline


- Proton Beam Monitors at the J-PARC Neutrino Extraction Beamline
- Some Issues with Present Proton Beam Monitors
- Upgrades for Proton Beam Monitors

J-PARC Neutrino Beamline Monitors

Primary Beamline Monitors




Final Focusing Section



- 5 CTs (Current Transformers) – monitor proton beam current
 - 50 BLMs (Beam Loss Monitors) – monitor proton beam loss
 - 21 ESMs (Electrostatic Monitors) – monitor proton beam position
- ↑ These are non-interacting and should work stably even at 1.3MW ↑

- ↓ These are interacting and may degrade at high beam power ↓
- 19→18 SSEMs (Segmented Secondary Emission Monitors) + 2 WSEMs (Wire SEMs) – monitor beam profile during beam tuning
 - 1 OTR (Optical Transition Radiation) Monitor – monitors proton beam position and profile at target
 - 1 MUMON (Muon Monitor) – continuously monitor muon beam

Proton Beam Intensity Monitor




- Uncertainty on the proton beam intensity yields flat uncertainty on the neutrino rate
 - Very important for cross section measurements
- Proton beam intensity is measured by Current Transformer (CT) mounted on the beam pipe
 - Beam intensity is proportional to current in wire wound around CT core
- Currently assign 2~3% error on beam intensity
- But:
 - Non-trivial to calibrate
 - Frequency dependence
 - “Test” coils unreliable
 - Need to worry about electronics calibration
 - ...
 - Calibration can gradually drift over time




How to Measure the Proton Beam Profile

Segmented Secondary Emission Monitor (SSEM)



- Protons hit $3 \times 5 \mu\text{m}$ Ti foils
- Secondary electrons are emitted from segmented cathode plane and collected on anode planes
- Compensating charge in each cathode strip is read out by ADC

Optical Transition Radiation Monitor (OTR)



- Foil in beam (Ti, etc)
- Optical Transition Radiation produced when charged particles travel between two materials with different dielectric constants
 - OTR light proportional to beam profile
 - Light detected by rad-hard camera in low-rad area


Why Is Non-Destructive (+ Minimally-Destructive) Proton Beam Monitoring Important?

- Standard monitors measure the beam profile by intercepting the beam – they are *destructive* and cause *beam loss*
 - Absolute amount of beam loss is proportional to beam power and volume of material in the beam
- Beam loss can cause :
 - Irradiation of and damage to beamline equipment
 - Increased residual radiation levels in the beamline tunnel
- Foils in the beam may degrade
 - Rate of degradation increases as the beam power increases
- The beam profile must be monitored continuously
 - So, R&D for J-PARC proton beam profile monitors that work well at high beam power is ongoing
 - Remote exchange procedure for existing profile monitors is also essential

SSEM Foil Discoloration

- SSEM19 is the most downstream SSEM and is used continuously
- SSEM19 foil inspection was performed in summer 2017 (downstream side) and fall 2018 (upstream side)
 - Significant discoloration of SSEM19 foils observed
 - No significant signal degradation, but plan to replace the monitor head in 2023

Downstream side after
 $\sim 2.3 \times 10^{21}$ Incident Protons





Upstream side after
 $\sim 3.2 \times 10^{21}$ Incident Protons




New WSEM Beam Profile Monitor

- New Wire Secondary Emission Monitor (WSEM) designed to measure proton beam profile in J-PARC neutrino beamline
- Monitor beam profile using twinned 25 μm Ti wires
 - Exact same principle as SSEM's but with reduced material in the beam \rightarrow reduced beam loss
 - C-shape allows monitor to be moved into and out of the beam while the beam is running (!)
 - Wires mounted at 45° so they can measure X and Y
 - Developed in collaboration with engineers at FNAL, supported as a US/Japan collaboration project




WSEM Performance, Status

- Beam loss by WSEM lower than SSEM by factor of ~ 10
- WSEM resolution, precision equivalent to SSEM
- No issue during long-term stress test
 - 160 hours in 460~475kW beam
 $\sim 5.6 \times 10^{19}$ incident protons



- Replaced SSEM18 with WSEM in December 2018
 - Since beam loss is significantly lower with WSEM, can use WSEM18 continuously in case of SSEM19 failure
 - Working stably since 2018

WSEM Plan




- Next steps for WSEM at J-PARC:
 - Add additional WSEM to final focusing section of beamline for further constraint of beamline optics at the target 2022(?)
 - Studies underway to understand impact of new monitor on beam optics constraint
 - Test carbon nano-tube (CNT) wires as more robust upgrade option
 - Procured $50\mu\text{m}$ and $25\mu\text{m}$ diameter CNT from Japanese company Hitz (high-quality, uniform surface)
 - Fabrication of CNT-mounted frame for J-PARC ongoing by engineer at FNAL now (US/Japan collaboration)
 - Install in J-PARC neutrino extraction beamline in 2023(?)


OTR Light Yield Decrease

- OTR foil discoloration seen after incident :
 - $\sim 5 \times 10^{20}$ POT on Ti Foil
 - $\sim 11 \times 10^{20}$ POT on Cross Foil
- Gradual decrease of OTR light yield
 - Due to radiation-induced darkening of leaded-glass fiber taper
 - Coupled to CID camera to shrink OTR image

Foil Discoloration :




OTR Normalized Light Yield (Stability) :




OTR Operational Issues

- Rotate disk remotely using motor to switch OTR foils
- Motor is stopped by micro-switch and plunger engages to disk flange when a foil is in position
- Recently had a few issues with OTR disk rotation:
 - Rotation torque became high – due to damage to Ti flange caused by stainless steel plunger ball ?
 - Micro-switch not activating at some disk positions



OTR Tests (Feb~March 2022)



- Dedicated test of OTR microswitch issue in early 2022
- Remote manipulation needed (spent Horn 1 and OTR)
- Small ($\sim 50\mu\text{m}$) misalignment between disk and microswitch found


OTR Tests (Feb~March 2022)



- Dedicated test of OTR microswitch issue in early 2022
- Remote manipulation needed (spent Horn 1 and OTR)
- Small ($\sim 50\mu\text{m}$) misalignment between disk and microswitch found

OTR Upgrades


- Decrease in OTR light yield observed
 - Due to radiation-induced darkening of optical component (fiber taper)
 - Upgrading optical system to use easily-replaceable fiber taper now (York University, TRIUMF)
- Useful to have backup procedure for OTR calibration + foil position information
 - Add holes to all OTR target foils – can be used to cross check foil position by back-lighting
 - Upgrade to thinner foil for improved stress tolerance
- Upgrading OTR readout for 1Hz operation, Windows → Linux (ICL)
- New OTR disk will be installed in the beamline in a few weeks, new DAQ will be used as main one from next beam run



OTR target disk

OTR Alignment/Installation

- New calibration light sources and support structure to confirm the OTR disk/foil position during OTR installation
 - Essential for confirming/reproducing new and old OTR disk alignment
 - Points along horn axis and is focused at the OTR disk foil
 - Laser/flashlight is held by rigid structure attached to the horn frame



Installation of new calibration light source on Horn 1 at J-PARC in April~May 2022


OTR Alignment/Installation

- Test installation of new OTR disk on mock Horn 1 by OTR group members in May 2022
- Actual installation of new OTR on new Horn 1 will take place in a few weeks
 - Horn 1 is new (not radioactive), but horn support module is used – actual installation work must be done using remote handling




Beam Induced Fluorescence (BIF) Monitor

- Uses fluorescence induced by proton beam interactions with gas injected into the beamline
 - Protons hit gas (i.e. N_2) inside the beam pipe
 - Gas molecules are excited or ionized by interaction with protons
 - Fluoresce during de-excitation with same profile as proton beam
- Continuously and non-destructively monitor proton beam profile
 - $5 \times 10^{-8}\%$ beam loss for 1m of gas at 10^{-2} Pa
 - $\sim 10^{-5} \times$ less beam loss than 1 SSEM
- Locally degrade vacuum level from $\sim 10^{-5} \rightarrow \sim 10^{-2}$ Pa to observe ~ 1000 BIF photons/spill at photodetector – Challenging!
 - Essential to optimize gas injection + light transport/detection
- Monitor development ongoing since 2015 – collaboration between KEK, IPMU/TRIUMF, Okayama Univ.



BIF Monitor Prototype




- Installed full working prototype monitor in J-PARC neutrino extraction beamline in 2019
 - Pulsed gas injection system
 - 2x optical systems (for horizontal + vertical readout)
- Took beam study data during 2020 + 2021 T2K beam runs
 - Fully non-destructive, so can take study data during physics run!



Camera (Horizontal) Measurement

Beam-induced background on

Image Intensifier :




Fit of X position and width:



- Clear beam signal across camera sensor
- Gaussian fit to extract beam position + profile

Image at camera after background subtraction (1 spill)


MPPC (Vertical) Measurement



- Clear vertical beam profile measured in optical fiber array after background subtraction + fiber-by-fiber transmission correction applied


Planned Upgrades to BIF

- Now upgrading housing + mechanical support for optical systems
 - Improve alignment of optical components
 - Reduce space used along beamline
- Also upgrading image intensifier – 2-stage MCP (1000x higher gain) + optimized photocathode (lower beam-induced background)
- Now also working to improve gas injection system
 - Required amount of injected gas to see clear BIF signal is $\sim 10\times$ more than original design
 - Possible to further reduce valve conductance to speed up gas pulse?
 - Additional pumping required?
- Aim to use BIF continuously (prescaled) during next beam run




Muon Monitoring

- Measure tertiary muon beam profile downstream of the decay volume, beam dump ($> \sim 5$ GeV muons)
 - Ensure alignment, healthiness of target, horns; proton beam position, angle at target; etc
- 2 redundant measurements of the muon beam profile, position using 7×7 arrays of sensors
 - Ionization chambers (IC)
 - Silicon photodiode sensors (Si)




Some issues :

The signal ratio of Si to IC (IC signal is stable within 0.2%)




IC signal / proton beam intensity vs. proton beam intensity



MUMON EMT

- Now developing EMT (PMT w/out photocathode) as more robust muon sensor option
 - Several dedicated beam tests carried out (@ELPH) – very promising results




NuFACT2022
(T. Honjo)


MUMON MCT

- Also developing MCT (MUMON Current Transformer) for muon sign measurement
 - First in-situ beam test carried out – made first muon beam polarity measurement at J-PARC!


Si detector




MCT





Neutrino mode



Anti-neutrino mode



data



The MCT signal was flipped in neutrino and anti-neutrino modes.

→ First observation of the muon polarity change at MUMON!

Future task: estimate the number of particles passing through the MCT using the signal.


Conclusion

- Upgrades to proton beam monitors:
 - Wire Segmented Emission Monitor (WSEM) – reduced beam loss
 - Working stably since 2018
 - New WSEM will be installed soon
 - Optical Transition Radiation Monitor (OTR)
 - Several upgrades in 2022
 - Installation of new OTR on new Horn 1 in 2022
 - Beam Induced Fluorescence Monitor (BIF) – non-destructive + robust monitor
 - Full prototype tested in 2020/2021
 - Upgrades to working prototype towards (pre-scaled) continuous monitoring in 2022
 - Muon Monitor (MUMON)
 - New EMT being tested as more robust/stable sensor option
 - MCT being tested for muon beam sign measurement

J-PARC Neutrino Beamline Upgrade Technical Design Report on arXiv :
<https://arxiv.org/abs/1908.05141>

Backup Slides


Measured Beam Loss Due to SSEMs



- Beam loss when SSEMs are IN is quite high
 - ~0.005% beam loss at each SSEM
- Can cause radiation damage, activation of beamline equipment
 - SSEMs upstream of the neutrino target station cannot be used continuously
 - SSEM1-18 are only used during beam tuning and optics checks

Beam Loss + Residual Radioactivity


Beam Loss and Residual Radiation



- The beam loss level must be kept approximately as low as the present loss level
- The beam loss and residual radioactivity are highest at the most upstream and downstream ends of the neutrino primary beamline


J-PARC NU SSEM Principle and Design

SSEM Principle



- Protons interact with foils
- Secondary electrons are emitted from segmented cathode plane and collected on anode planes
- Compensating charge in each cathode strip is read out as positive polarity signal

J-PARC NU SSEM




- Single anode plane between two stripped cathode planes
- 5 μm thick Ti foils

SSEM19 must be used continuously

SSEM19


- For continuous monitoring of beam position, width at the beam window + target
 - A beam abort interlock signal is fired in order to avoid potential damage to the beam window/target if :
 - Beam density @target $N_p/(\sigma_x \times \sigma_y) < 2 \times 10^{13}$ ppp/mm²
 - Beam position becomes significantly offset from centered
- Originally, SSEM lifetime only estimated up to $\sim 10^{20}$ protons/cm²
- However, no issue seen at $\sim 3.8 \times 10^{21}$ protons (4×4mm beam spot)
- Important to monitor degradation as total integrated POT increases




OTR Stability

Foil Discoloration :

- OTR foil discoloration seen after incident :
 - $\sim 5 \times 10^{20}$ POT on Ti Foil
 - $\sim 11 \times 10^{20}$ POT on Cross Foil
- Gradual decrease of OTR light yield
 - Originally believed due to foil degradation...
 - Actually due to radiation-induced darkening of leaded-glass fiber taper
 - Coupled to CID camera to shrink OTR image




OTR Normalized Light Yield (Stability) :



WSEM Beam Loss Check

- Prototype WSEM installed in J-PARC neutrino beamline 2016~
- Checked performance during various beam tests
- Beam loss by WSEM lower than SSEM by factor of ~10
 - Note: BLM acceptance is different for SSEM vs WSEM
 - Residual radiation @SSEM18 is 1.2mSv/hr at 475kW due to backscatter from TS
 - Residual radiation @WSEM due to continuous use at 465kW was 300 μ Sv/hr



Loss due to WSEM vs that due to neighboring SSEM :



Monitor	Strip Size	Area in Beam (mm ²)	Measured Signal (a.u.)	Volume in Beam (mm ³)	Measured Loss (a.u.)
SSEM	2~5mm×5 μ m	7.07	60300	0.106	872
WSEM	25 μ m ϕ ×2	0.24	2300	0.007	112
Ratio					
SSEM/WSEM	—	29.5	26	15.1	7.8



SSEM18→WSEM Exchange

- Replaced SSEM18 with WSEM in December 2018
 - Since beam loss is significantly lower with WSEM, can use WSEM18 continuously in case of SSEM19 failure
 - In use stably since 2018




OTR Principle and Design

- Continuously monitors beam profile at the target, essential for beam tuning
- OTR light is produced when charged particles travel through foil
- T2K OTR monitors backwards-going light from 50- μm -thick Ti foil directly upstream of the target
 - Light is directed to TS ground floor by a series of 4 mirrors and then monitored by a rad-hard CID camera
- T2K OTR has rotatable disk w/ 8 foil positions; currently :
 - 4x Ti alloy (for physics running)
 - 1x ceramic (for low-intensity tuning)
 - 1x cross-pattern holes \leftarrow current foil
 - 1x calibration holes (for calibration by back-lighting)
 - 1x empty




OTR Upgrades

- Decrease in OTR yield observed
 - Upgrade optical system to use easily-replaceable (inexpensive) fiber taper – regularly replace as it becomes dark
- Useful to have backup procedure for OTR calibration + foil position information
- Add holes to all OTR target foils
 - Can be used to cross check foil position by back-lighting
 - Need to ensure foil robustness including additional holes – FEM simulations underway
- Upgrade foil to use more robust, reflective material ?
 - Now using Ti-15-3-3-3 alloy
 - Considering possible benefit of moving to carbon (graphite) or Ti grade 5 (Ti-6Al-4V)
- Upgrade OTR readout for 1Hz operation + Windows→Linux




BIF Gas Injection System

- Goals :
 - Safely inject specified amount of N_2 gas into the beamline at the beam timing
 - Stop injection if trouble
 - Minimize injected gas amount to maintain ion pump lifetime
 - Monitor injected gas amount + gas profile at BIF interaction point
- BIF gas system consists of :
 - 2 pulse valves with a buffer chamber between them
 - Control system :
 - 1st pulse valve fills buffer chamber when pressure becomes low
 - 2nd pulse valve pulsed using beam trigger – injection length + timing can be precisely controlled
 - Interlock system closes pneumatic valve if pressure exceeds threshold
 - Vacuum gauges
- Gas system generally has been working stably
- Unfortunately, required amount of gas injected to see clear BIF signal is $\sim 10\times$ more than original design



Jan 2020 valve line photo


Optical System Overview



- Simultaneously observe BIF light in 2 independent optical systems
- Windows at top + right side of beampipe can be used for calibration LEDs or additional detection systems

BIF Gas Injection System



- Goals :
 - Safely inject specified amount of N_2 gas into the beamline at the beam timing
 - Stop injection if trouble
 - Minimize injected gas amount to maintain ion pump lifetime
 - Monitor injected gas amount + gas profile at BIF interaction point
- BIF gas system consists of :
 - 2 pulse valves with a buffer chamber between them
 - Control system :
 - 1st pulse valve fills buffer chamber when pressure becomes low
 - 2nd pulse valve pulsed using beam trigger – injection length + timing can be precisely controlled
 - Interlock system closes a pneumatic valve if beamline or valve line pressure exceeds threshold
 - Cold cathode vacuum gauges in the main beamline precisely measure pressure



Jan 2020 valve line photo
(was upgraded for 2021 run,
further upgrades also planned)

Pulsed Gas Injection + Upgrade Plans


Pressure by vacuum gauges + gas pulse mapped out by BIF light:



- Gas system generally has been working stably
 - Can control injected amount of gas by adjusting valve open time + buffer chamber pressure
 - Tested various amounts of injected gas, scanned gas injection timing relative to beam timing
- Unfortunately, required amount of gas injected to see clear BIF signal is $\sim 10\times$ more than original design
 - Due to broad/slow gas pulse due to low valve conductance
 - Increased conductance in 2021, improved compared to 2020 run
 - Considering ways to: further improve valve conductance, improve photon detection; or, prescale BIF measurement


Is It Really BIF Light ?

- Yes !
- Signal size fully correlated with amount of injected gas
- No signal observed without gas injection
- Signal observed in both optical readout systems simultaneously



BIF Camera (Horizontal) Optical System


- Horizontal beam position + profile measured by:
 - 2x plano-convex lenses to focus BIF light onto
 - Micro-Channel Plate (MCP) based gateable Image Intensifier
 - Coupled to radiation-hard CID camera by silica fiber taper
 - Installed under the beamline at the BIF interaction point
 - Custom camera readout system developed at Imperial College London for T2K OTR
- Plan to upgrade image intensifier to one with a 2-stage MCP (1000x higher gain) + optimized photocathode (lower beam-induced background) for next run







BIF camera system

BIF Background Mitigation in Optical Fibers



- During initial BIF test runs, signal to beam-induced background ratio for optical fiber + MPPC readout arm was close to $\sim 1:1$!
- Reduced background size to $\sim 1/12$ of signal by optical filtering



BIF Horizontal Measurement Stability




BIF Vertical Measurement Stability



- Position and width measurements relatively stable
- Fluctuations can be due to true changes in beam properties, or statistical fluctuation yielding insufficient photons for precise profile reconstruction


BIF Optical Fiber + MPPC (Vertical) Optical System



- Focus light from viewport on beampipe onto array of optical fibers
- Transport light away from high radiation environment near beampipe to optical sensors in lower-radiation sub-tunnel
 - Couple each fiber to MPPC
 - Inexpensive, fast, high gain
 - But not radiation hard
- Challenge : optimize transmission and collection efficiency to increase number of collected photons (expected)
- Unexpected challenge : beam-induced noise on optical fibers
 - Suspect Cherenkov light (on-timing) and neutrons (off-timing)
 - Mitigate by optical filtering


BIF Optical Fiber + MPPC (Vertical) Optical System

Optical fibers installed near
beamline:




Installed 2x new fibers in
Feb 2021

Optical fibers read out by MPPC array(s) at
subtunnel :



Top view



← Fiber layout at
beamline side



New fiber layout: ~ x2 No. of fibers

Background Mitigation in Optical Fibers

- During initial BIF test runs, signal to beam-induced background ratio for optical fiber + MPPC system was close to $\sim 1:1$
- Reduced background size to $\sim 1/12$ of signal by optical filtering


**S/B ratio depends on gas pressure pump*

One filter used
to select signal
w/ narrow wavelength



Bkg. \Downarrow by $\times 18.7$
Sig. \Downarrow by $\times 2.5$

Optical filter is effective to mitigate
background in the optical fiber



Bkg. ~ 20 p.e.


Sig. ~ 250 p.e.

**Signal/background
 $\sim 10:1$**

Other Measurements by MPPC Readout

- Several other important measurements enabled by MPPC readout
 - J-PARC beam has world's largest number of protons per bunch – $\sim 4 \times 10^6$ V/m beam-induced space-charge field
 - Concern that ionized particles would move in beam space-charge field
 - Measure time dependence of BIF profile by fast readout
 - Also interesting to measure optical spectrum of BIF light (+ beam-induced background light) using various optical filters

Pessimistic simulation result



Preliminary measurement

